











The Nu-Heat underfloor heating range

Heating homes in the best possible way

		System types - covering a wide range of applications				Specialist retrofit systems - where height build-up/heat output are important		Electric UFH Single zone kits	
		Screed	FastDeck®	Suspended timber	Acoustic	LoPro® Lite	LoPro®10 	LoPro® Max	ElectroMat®
									
		The heating tube is clipped into standard insulation and held in place with Cliptrack® before screed is poured or trowel-applied.	Patented injection moulded plastic panels retain and push pipe up to high-density aluminium-laminated gypsum panel	UFH tube is fed through pre-notched or drilled joists and held securely with patented ClippaPlate®	UFH tube is integrated into a floor cassette comprising construction elements proven to improve acoustic performance <i>Robust Details available</i> 	High-density EPS LoPro® Lite panel is laid over the existing floor and metal heat diffuser plates are then positioned into the grooves	Pre-routed gypsum boards holding the UFH tube in place are laid over the existing floor.	Castellated panels hold the heating tube in place before being covered by a specialist self-levelling compound, LoPro®QuickSet®	Waterproof 1-18m ² electric UFH kits with patented de-coupling membrane and flexible cable
PROJECT SUITABILITY	Extensions	✓	✓	✓		✓	✓	✓	✓
	New-build	✓	✓	✓	✓	✓	✓	✓	✓
	Renovations	✓	✓*	✓*	✓	✓	✓	✓	✓
	Ground floors	✓	✓	✓	✓	✓	✓	✓	✓
	Upper floors	✓	✓	✓	✓	✓	✓	✓	✓
	Apartments	✓	✓		✓	✓	✓	✓	✓
	Office-to-residential	✓	✓		✓	✓	✓	✓	✓
Installed over floor or under floor?	In sub-floor, over floor insulation on either concrete or beam and block floor	Directly over timber, solid floor deck or screed; ground floors must have insulation.	Under the floor deck, either between joists or straddling them	Dependent on system	Directly over sub-floor/structural deck	Directly over timber or solid floor deck	Directly over timber or solid floor deck	Directly over timber or solid floor deck	
Installation schedule	1st FIX	1st FIX & 2nd FIX	1st FIX	1st FIX & 2nd FIX	1st FIX	2nd FIX	2nd FIX	2nd FIX	
Full height build-up (exc. floor coverings & insulation)	50-65 mm	34 mm	0 mm	Dependent on system	Dependent on system	15 mm	22 mm	5.5 mm	
Heat output**	very high Up to 120W/m ²	high Up to 90W/m ²	medium Up to 70W/m ² / high Up to 100W/m ²	medium Up to 70W/m ² / very high Up to 120W/m ²	medium Up to 80W/m ² / very high Up to 120W/m ²	high Up to 110W/m ²	very high Up to 150W/m ²	very high Up to 150W/m ²	
Heat conduction method	Through screed	Aluminium-laminated gypsum panels	Metal heat diffuser plates	Dependent on system	Metal heat diffuser plates	Gypsum panels	Specialist LoPro®QuickSet self-levelling compound	Dependent on system	
Fastflo tube size	14 mm or 17 mm	14 mm	14 mm	10 mm or 14 mm	10 mm	10 mm	10 mm or 14 mm	N/A	
Drying time	1 day/mm screed	No drying necessary	No drying necessary	Dependent on system	No drying necessary	8 hours - foot traffic 72 hours - floor coverings	8 hours - foot traffic 72 hours - floor coverings	Tile adhesive 12 hours - foot traffic	
Nu-Heat system codes	SC14, SC17, SL17, SCB14, SCS14, SL14, SM14, SM17, SMC14, SP14, SPI14, SSE14, SSE17, SSP14, SSP17, SST14, SST17	FDC14, FDT14	TPBA14, TPBAK14, TS14, TSB14, TSG14	ADPK14, ADPKC14, AKA14, APC14, APT14, ASC14, ASCE14, ASL14, ASLE14, AST14, ATAC14, ATAK14, ATPAK14, ALPB10, ALPFC10, ALPFT10, ALPRAF10, AP14	LPLT10, LPLCB10	LoPro®10	LoPro®Max LoPro®Max14	eUFH* <small>*Dependent on kit size</small>	

*As long as up to Part L Regs.
**Values subject to limitation in accordance with current regulations.